BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Re Construction of cement concrete road at Jodidar Narasimhaiah layout at Bagalagunte in ward no. 14

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor Sri M/s. Sri Venkateshwara Enterprises	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	111	91.7	Rupees Ninety One and Seventy Paise Only
2	Removing B.S slab of Drain and stacking complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	99.9	69.33	Rupees Sixty Nine and Thirty Three Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Cum	24.98	5442.77	Rupees Five Thousand Four Hundred Forty Two and Seventy Seven Paise Only
4	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 7.5 cms thick complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	399.6	702.29	Rupees Seven Hundred Two and Twenty Nine Paise Only
5	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications.complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Cum	24.05	5906.86	Rupees Five Thousand Nine Hundred Six and Eighty Six Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

6	Providing and construction load bearing wall with solid concrete block of Size 400x200x200mm having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges scaffolding, curing, hire charges of machineries etc., complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	296	1047.85	Rupees One Thousand Forty Seven and Eight Five Paise Only
7	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 10 cms thick complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	333	871.16	Rupees Eight Hundred Seven One and Sixteen Paise Only
8	Providing two line dressing to granite stone slab/granite stone masonry as per specification. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	333	1016.53	Rupees One Thousand Sixte and Fifty Three Paise Only
9	Providing Machine cutting to BS slabs complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Rmtr	1850	52.3	Rupees Fifty Three and Thir Paise Only
10	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Nos	823	417.35	Rupees Four Hundred Seven and Ten Paise Only
11	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	148	29.08	Rupees Twenty Nine and Eight Paise Only
12	Providing and applying spary painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materiasl, labour, complete as per specifications. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	148	73.81	Rupees Seven Three and Eigh One Paise On

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

	rifying the existing granular road surface to a depth of mm and disposal of scarified material within all lifts and ds upto 1000 metres complete as per specifications. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	1740	22.37	Rupees Twenty Two and Thirty Seven Paise Only
14	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Cum	240.75	5442.77	Rupees Five Thousand Four Hundred Forty Two and Seventy Seven Paise Only
15	Cement Concrete Pavement:- Construction un-reinforced plain cement concrete pavement, thickness as per design over a prepared sub base with OPC cement or any other type as per clause 1051.2.2. with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrance, sealant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grades as per drawing complete as per specifications. M20 (at 300 kg per cum coarse aggregate @ 0.64 cum and fine aggregate @ 0.43 cum) complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Cum	240.75	5811.81	Rupees Five Thousand Eight Hundred Eleven and Eighty One Paise Only
16	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift complete as per specifications.complete as per the direction of Engineer-in-charge of the work.	Sqm	1605	100.65	Rupees One Hundred and Sixty Five Paise Only

Rupees One Thousand Forty Seven and Eighty ive Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

17	Providing groove cutting for width of 5mm to 10mm and depth 80mm 100mm including cost of cutting machine, generator & HOM of machinery, including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc , including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc , including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications for concrete pavement complete as per specifications complete as per the direction of Engineer in charge of the work	Rmtr	342	128 6	Rupees One Hundred Twenty Eight and Sixty Paise Only
18	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4KM	Cum	981	87 49	Rupees Eighty Seven and Forty Nine Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division.

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner